

Walking and Bicycling Counts: Collaboratively Collecting & Using Non-Motorized Data in Minnesota

Michael Petesch | Pedestrian and Bicyclist Data Coordinator

6/12/2020



mndot.gov

Agenda



- Background
 - personal
 - programatic
- Permanent Program
- Portable Program
- Challenges
- Strategic Plan
- Progress



Michael Petesch works for the Minnesota Department of Transportation managing and coordinating bicycle and pedestrian data collection efforts.

He strives to make it safer, easier, and more convenient for people of all ages and abilities to walk and bike where they need to go.

Michael's Background







2011 – 2013 \$21mil Federal Non-Motorized Transp. Pilot Program

- 6 Manual / month
 - A few automated

2013 – 2016 Bike & Ped Data Collection Initiative

- 200+
 Automated
 Counts
- 5 Formats


2016 – NOW Bike & Ped Data Collection Programs


- 22 Perm
- 18 Portable
- ~100 temp sites
 - 230+ Manual Count Sites

Program Background



DEATHS








Program Background

3-part research study (2012-2016) called the "MN Bicycle and Pedestrian Counting Initiative"

- Methodologies: Test and develop data collection & factoring methods with a few devices and manual counts.
- Implementation: Purchase and test various equipment, install many locations and validate counts. Show trends and travel patterns.
- Institutionalization: Imbed work in MnDOT, purchase and install more equipment, work with partners to collect more data.








MnDOT's Pedestrian and Bicyclist Data Collection Program

MnDOT PROGRAM


PERMANENT





PORTABLE





Permanent Sites

- Joint Effort
- Trends
- Factoring
- Partnerships
- Continuous
- 27 at 21
- 13 trail
 8 road

Voor	Counters	Sites	
Year	Installed	Added	
2013	4	2	
2014	5	4	
2015	6	4	
2016	11	9	
2017	3	3	
Grand Total	29	22	










Mankato – Vet's Bridge Civ


Permanent Sites


Total Traffic Volumes Across All Reference Sites That Count Both Bikes and Peds, 2014-2017




Pedestrian Sites	Annual Peds	AADP	Jan ADP	July ADP
Brainerd – Paul Bunyan Tr	13,568	37	15	64
Brooklyn Park – Rush Creek Tr	36,186	99	33	135
Cass Lake – Migizi Tr	3,956	11	4	20
Duluth – Lakewalk Tr	304,123	833	315	1,634
Lanesboro – Root River Tr	19,822	54	11	114
Mpls – West River Greenway	249,973	685	222	1,105
Moorhead – Highway 75 Tr	19,049	52	51	82
St Cloud – Beaver Island Tr	27,265	75	29	65
St Paul – Jackson St path	128,399	352	186	447
Grand Total	802,340	2,198	867	3,665

Permanent Sites





2017 Hourly Pedestrian Volumes





Portable Equipment

- 8 Sets
- Training Material
- Free
- Check out &
 Return forms
- Local Needs
- Wide Coverage
- Public Data

Return Form for MnDOT's Bicycle and Pedestrian Counting Equipment

-				-	
	а	t	ρ	*	
-	u	-	-		


Jun 🗘	0	8 🗘	2	020	\$	
-------	---	-----	---	-----	----	--

Choose the Equipment Host in your MnDOT District:*

District 1 * Charlie Moore * ARDC * 21	18-529-7553 * cmoore@ardc.org * Duluth, MN	
Borrower's (Your) Name *		
First Name	Last Name	
Tubes & Pyro Installed Together or Sepa	arately?*	
Reason for count: *		
Choose one		\$
What Difference Will This Data Make?	*	

Tubes & Py	ro Install	ed Togeth	ner or Separately?*	
Reason for	count:*			
Choose one	<u>.</u>			\$
What Diffe	rence Wi	ll This Dat	ta Make?*	
			400	, 0/40
Check-out	Date:*			
\$	\$	¢		
Installation	Date & T	ime:*		
\$	\$	\$		
\$:	\$	\$		
Removal Da	ate & Tim	e:*		
\$	\$	\$		
\$:	\$	\$		
		·		
Return Dat] 🛶	
\$	\$	\$		

\$



https://www.arcgis.com/home/webmap/viewer.html?webmap=e98c225ff41249e88ae59a25c596170c&extent=-99.2088,43.29,-87.739,49.4581

MnDOT Portable Sites

Year	Cities	Sites	Installs
2015	4	9	9
2016	7	13	17
2017	16	21	34
2018	21	26	32
2019	10	19	26
2020	7	11	12
Total	65	99	140

Challenges

- Many partners & agendas
- Lots of data & formats
- **QA / QC**
- Factoring & Estimates
- Share Data
- Data-Driven Decision Making
- Resources (< motor vehicle)
- Expansion

Strategic Plan


DEPARTMENT OF TRANSPORTATION

Table of Contents

INTRODUCTION
PROGRAM BACKGROUND
Nonmotorized Counting Program Concepts and National Guidance
Counting Strategies and Equipment Present in Minnesota8
Benefits of Counting Pedestrians and Bicyclists11
Challenges of Minnesota's Data Program
Program Overview Conclusions
DATA PROGRAM GOALS FOR COUNTING PEOPLE WALKING AND BICYCLING
Purpose and Need16
Goals17

https://www.dot.state.mn.us/bike/documents/planningresearch/strategic-plan.pdf

STRATEGIES AND ACTIONS
Strategy 1: Develop a strategic deployment plan for MnDOT-owned and managed pedestrian and bicyclist counters
Strategy 2: Build a central data warehouse to store data from MnDOT and partner agencies and organizations
Strategy 3: Develop factor groups, adjustment factors, and models based on MnDOT data capacities and needs
Strategy 4: Lead inter-agency coordination around pedestrian and bicyclist count data collection and use
Strategy 5: Monitor and communicate count data performance measures and applications internally and externally
CONCLUSIONS AND NEXT STEPS
APPENDIX 1: GOALS OF THE TASKFORCE AND PROGRESS
Goal 1: Central data repository
Goal 2: Factor groups and expansion factors
Goal 3: Develop metrics and performance measures40
Goal 4: Future Planning
APPENDIX 2: COMBINED STRATEGIES AND ACTIONS TABLE



Strategy 1: Strategic Deployment

Inputs:


- Greater MN
- Bicycle Investment Routes
- Trunk Highways
- Paved Shoulders (≥ 5ft)
- Bridges and Culverts
- USBR 41 & 45
- State Trails
- Off Road Bicycle Trails
- Population Centers
- Native American Reservations
- Public Suggestions

Strategy 2: Build Data Warehouse

DEPARTMENT OF TRANSPORTATION


D7 | Mountain Lake – Lawcon Park Recount Period Analyzed: Tuesday, June 26, 2018 to Friday, July 13, 2018






 Pre warehouse count "directory" with data from MnDOT, Hennepin County, MnDNR, City of Minneapolis, and others.

IT Project




Falls

Strategy 3: Develop Factors (DOY)



Strategy 4: Lead & Convene





2020 compared to MADW of previous 3yrs.

Total % Change by Site and Extent (3/13 – 5/31/20)

EXTENT	Total
🖃 Greater MN	68.45
\pm D1 Duluth Lakewalk Trail	29.49
\pm D2 Cass Lake Migizi Trail	42.12
\pm D3 Brainerd Paul Bunyan Trail	68.29
\pm D3 St Cloud Beaver Island Trail	131.08
\pm D4 Moorhead TH75 Trail	50.12
\pm D6 Lanesboro Root River Trail	49.09
\pm D7 Mankato Veterans Mem. Bridge	41.14
\pm D8 Hutchinson Luce Line Trail	103.76
\pm D8 Willmar Lakeland Drive	101.50
Metro	32.31
\pm Metro Brooklyn Park Rush Creek Trail	178.09
\pm Metro Minneapolis Central Ave	-9.35
\pm Metro Minneapolis Franklin Tower	0.01
🕀 Metro Minneapolis Park Ave Northbound	-41.87
\pm Metro Minneapolis West River Greenway	42.97
া Metro Orono Shadywood Dr	128.16
া Metro St Paul Jackson St	-24.42
🕀 Metro St Paul Summit Ave (all loops)	-8.72
Total	51.52



Alexandria: Demo Projects





<u>St Paul:</u> Ped / Bike Bridge Reconstructions



Gap in the fence that 35x

more people use than the

x-walk about an 1/8mi

south

Resulted in \$300k sidewalk and **HAWK** system funding and will include a people counter

TH 169 near Mille Lacs Casino – A *photo collage* of people traveling to destinations



Thank you again!

Michael Petesch

michael.petesch@state.mn.us

Jake Schutt

Suzy Scotty

jake.schutt@state.mn.us

suzanne.scotty@state.mn.us

MnDOT Pedestrian and Bicyclist Count Program